


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

TWP - North Randall

1. Location of well:	County <b>Thomas</b>	Fraction <b>NE 1/4 NE 1/4 SE 1/4</b>	Section number <b>32</b>	Township number <b>T 8 S R 32 E/W</b>	Range number
2. Distance and direction from nearest town or city: <b>Mingo- 3ME; 2 1/2 N</b>			3. Owner of well: <b>Henry Siebert</b> R.R. or street: <b>RFD #2 - Colby, Kansas 67701</b> City, state, zip code: <b>Mingo, Kansas</b>		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. <b>30</b> in. Completion date <b>6-3-76</b> Well depth <b>170</b> ft.
Clay			0	45	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Coarse Sand & Gravel			45	77	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Clay & Sand Streaks			77	104	9. Casing: Material <b>Steel</b> Height: Above <b>25</b> ft. below <b>25</b> ft. Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>.188</b> lbs./ft. Dia. <b>12</b> in. to <b>100</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>#7</b>
Coarse Sand & Gravel			104	113	10. Screen: Manufacturer's name <b>Brown</b> Type <b>Regular</b> Dia. <b>12</b> Slot/gauze <b>10</b> Length <b>60</b> Set between <b>100</b> ft. and <b>160</b> ft. <b>10</b> Cook ft. and <b>170</b> Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/4 x 5/8</b>
Clay			113	120	11. Static water level: <b>120</b> ft. below land surface Date <b>5/8/76</b>
Coarse Sand & Gravel			120	133	12. Pumping level below land surfaces: <b>165</b> ft. after <b>2</b> hrs. pumping <b>270</b> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>270</b> g.p.m.
Cemented sand & Gravel & Sandstone Streaks			133	139	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Sandy Clay & Sand & Gravel Streaks			139	150	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> Inches above grade
Coarse Sand & Gravel & Sandstone			150	156	15. Well grouted? <input checked="" type="checkbox"/> & Clay With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Cemented Sand & Gravel & Sandstone			156	163	16. Nearest source of possible contamination: ft. <b>40</b> Direction <b>N</b> Type <b>Farm</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Ochre & Sand Streaks			163	170	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <b>HH6H620</b> HP <b>20</b> Volts <input type="checkbox"/> Length of drop pipe <b>168</b> ft. capacity <input type="checkbox"/> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Ochre & Shale			170		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Western Well &amp; Pump 245</b> Business name <b>Box 852 Colby, KS 67701</b> License No. <input type="checkbox"/> Address <b>Dolly Berry</b> Date <b>8/20/76</b> Signed <input type="checkbox"/> Authorized representative
18. Elevation:			19. Remarks: <b>ROCK 163'</b>		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5