

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well: County Thomas Township name Morgan Fraction South - line of N.E. 1/4 Section number #11 Town number T 8 S Range number R 33 W

Distance and direction from nearest town or city: 1 1/2 mile south of  
& 2 miles East of Colby, Kansas  
Street address of well location if in city:

3 Owner of well: Vacin Farms Inc.  
Address: Colby, Kansas 67701

Locate with "X" in section below: Sketch map:

N  
W E  
S  
1 Mile

4 Well depth: 260 ft. Date of completion 3-1-75  
Well diameter 16 in.

5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug  
☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary

6 Use: ☐ Domestic ☐ Public supply ☐ Industry  
☒ Irrigation ☐ Air conditioning ☐ Commercial  
☐ Test well

7 Casing: Material Steel Height: above/below  
Threaded ☐ Welded ☒ Surface 12 in.  
Digm. 16 in. to 260 ft. depth Drive shoe? ☐ Yes ☒ No  
\_\_\_\_\_ in. to \_\_\_\_\_ ft. depth

8 Screen: W.A. Brown  
Manufacturer Bridge Dia. 16  
Type Bridge Slot/gauze 1/8 Length 2  
Set between 170 ft. and 250 ft.  
Fittings: 10' of cook on bottom  
Gravel pack ☒ Yes ☐ No Size range of material 1/8x3/8

9 Static water level: 125 ft. below land surface Date 3-1-75

10 Pumping level below land surfaces:  
19 ft. after 2 hrs. pumping 1400 g.p.m.  
\_\_\_\_\_ ft. after \_\_\_\_\_ hrs. pumping \_\_\_\_\_ g.p.m.  
Estimated maximum yield 2500 g.p.m.

11 Water sample submitted:  
☐ Yes ☒ No Date \_\_\_\_\_

12 Well head completion:  
☐ Pitless adapter 12 inches above grade

13 Well grouted? ☒ Yes ☐ No  
☒ Neat cement ☐ Bentonite  
Depth: From 0 ft. to 10 ft.

14 Nearest source of possible contamination:  
ft. 2000 Direction S.E. Type Septic Tank  
Well disinfected upon completion? ☐ Yes ☒ No

15 Pump: ☐ Not installed  
Manufacturer's name Byron Jackson  
Model number H7033 HP 100 Volts \_\_\_\_\_  
Length of drop pipe 230 ft. capacity 900 g.p.m.  
Type:  
☐ Submersible ☒ Turbine  
☐ Jet ☐ Reciprocating  
☐ Centrifugal ☐ Other

16 Remarks: elevation 3135 (top)  
Topography:  
☐ Hill  
☐ Slope  
☒ Upland  
☐ Valley

17 Water well contractor's certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
Western Well & Pump Inc.  
Business name License No. \_\_\_\_\_  
Address P.O. Box 852, Colby 245  
Signed Ray F. Jensen Date 3-20-75  
Authorized representative

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5