


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

SW-SE-NW BDC

1 Location of well:	County Thomas	Township name Morgan	Fraction Center of So.	Section number #11	Town number T 8 S	Range number R 33 W
Distance and direction from nearest town or city: 1 1/2 mile South & 2 miles East of Colby, Kansas				3 Owner of well: Vacin Farms Inc. Address: Colby, Kansas 67701		
Locate with "X" in section below: 				Sketch map:		
2				4 Well depth: 290 ft. Date of completion: 3-27-75 Well diameter: 16 in.		
Type and color of material				5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Soil & Clay				6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well		
Clay & sand streaks				7 Casing: Material Steel Height: above/below Threaded ☐ Welded ☒ Surface 12 in. Digm. 16 in. to 29 ft. depth Drive shoe? ☐ Yes ☒ No _____ in. to _____ ft. depth		
Sandy clay				8 Screen: W. A. Brown Manufacturer Bridge Dia. 16 Type 1/8 Length 2 Slot/gauze 200 ft. and 280 ft. Set between 200 ft. and 280 ft. Fittings: 10' of cook on bottom Gravel pack ☒ Yes ☐ No Size range of material 1/8x3/8		
Fine to coarse sand & gravel				9 Static water level: 123 ft. below land surface Date 2-27-75		
Sandy clay				10 Pumping level below land surfaces: 190 ft. after 2 hrs. pumping 1475 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 2500 g.p.m.		
Cemented sand & sandy clay				11 Water sample submitted: ☐ Yes ☒ No Date _____		
Fine to coarse sand & gravel				12 Well head completion: ☐ Pitless adapter 12 inches above grade		
Clay				13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ _____ Depth: From 0 ft. to 10 ft.		
Fine to coarse sand & gravel				14 Nearest source of possible contamination: ft. 5000 Direction S.E. Type Septic tank Well disinfected upon completion? ☐ Yes ☒ No		
Cemented sand				15 Pump: Byron Jackson Not installed Manufacturer's name 7035 HP 100 Volts _____ Model number 230 ft. capacity 900 g.m.p. Length of drop pipe _____ ft. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Fine to coarse sand & gravel				16 Remarks: elevation 3147 (TUP) BROOK 288'		
Shale (use a second sheet if needed)				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Western Well & Pump Inc. Business name P.O. Box 852, Colby 245 License No. _____ Address _____ Signed Ray E. Senior Date 3-20-75 Authorized representative		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5