

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Thomas	NE 1/4 NE 1/4 NE 1/4	5	T 8 S	R 34 E W

Distance and direction from nearest town or city street address of well if located within city?

Lot 6 Block #3 Country Acre Estate

2 WATER WELL OWNER:	Stan Strange	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	960 E. 6th	Application Number:
City, State, ZIP Code :	Colby, Ks. 67701	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 205 ft. ELEVATION:
	Depth(s) Groundwater Encountered: 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL: 104 ft. below land surface measured on mo/day/yr
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter: 8 in. to 205 ft., and in. to ft.
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes No X	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter: 4.5 in. to 165 ft. Dia.	in. to ft. Dia.	in. to ft. Dia.	Threaded
Casing height above land surface: 18 in., weight 2.38 lbs./ft. Wall thickness or gauge No. 248			
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
SCREEN-PERFORATED INTERVALS: From 165 ft. to 205 ft. From ft. to ft.			
GRAVEL PACK INTERVALS: From 20 ft. to 205 ft. From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 0 ft. to 20 ft. From ft. to ft.				
What is the nearest source of possible contamination: NONE				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? How many feet?				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Surface	130	132	Sandy Clay & Caliche
2	18	Loess	132	140	Fine to Med Sand & Gravel
18	32	Sandy Clay w/Caliche Strks.			W/Clay & Caliche
32	36	Caliche & Clay	140	142	Sandy Clay
36	48	Sandy Clay & Caliche	142	152	Med. Sand & Gravel w/Clay
48	52	Med. Sand w/Clay & Caliche			& Caliche
52	58	Sandy Clay w/Caliche	152	158	Caliche w/Clay Strks
58	60	Sandy Clay & Caliche w/Sand	158	168	Cemented Sand w/Sand Strks.
60	72	Fine to Med. Sand w/Clay &	168	173	Med. Sand & Gravel
72	85	Fine Sand w/Clay Gravel	173	177.5	Cemented Sand w/Sand Strks/
85	87	Med. Sand w/Clay Strks.	177.5	188	Med. Sand & Gravel
87	100	Med. Sand & Gravel w/Some	188	192	Cemented Sand
100	109	Sandy Clay & Caliche w/Some Sand Strks.	192	200	Sandy Clay w/Sandy Strks.
109	130	Med. Sand & Gravel w/Clay Lenses	200	205	Med. Sand w/Clay Strks.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-19-94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 554 This Water Well Record was completed on (mo/day/yr) 5-23-94 under the business name of Woofter Pump & Well, Inc. by (signature) <i>[Signature]</i>
--