


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Thomas</b>	Fraction <b>Center</b> 1/4 <b>NE</b> 1/4	Section number <b>10</b>	Township number <b>T 8 S</b>	Range number <b>R 34 E/W</b>
2. Distance and direction from nearest town or city: <b>From Colby</b> <b>1 1/2 South; 2 1/2 West</b> Street address of well location if in city:			3. Owner of well: <b>Ferguson Trust</b> R.R. or street: City, state, zip code: <b>Colby, Kansas</b>			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 		6. Bore hole dia. <b>30</b> in. Completion date <b>8-7-76</b> Well depth <b>271</b> ft.	
5. Type and color of material			From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Clay			0	52	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Sand & Gravel & Clay			52	99	9. Casing: Material <b>Steel</b> Height: Above or <del>Below</del> <b>12</b> in. Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>.188</b> lbs./ft. Dia. <b>16</b> in. to <b>181</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>#7</b>	
Clay			99	116	10. Screen: Manufacturer's name <b>Brown</b>	
Coarse Sand & Gravel			116	124	Type <b>Regular</b> Dia. <b>16"</b> Slot/gauze <b>10</b> Length <b>80'</b> Set between <b>181</b> ft. and <b>261</b> ft. <b>10' Cook 261</b> ft. and <b>271</b> ft.	
Clay			124	132	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>5/8 30% #1</b>	
Coarse Sand & Gravel			132	144	11. Static water level: <b>146</b> ft. below land surface Date <b>8-10-76</b>	
Sandy Clay			144	149	12. Pumping level below land surfaces: <b>266</b> ft. after <b>2</b> hrs. pumping <b>1804</b> g.p.m. <b>266</b> ft. after <b>2</b> hrs. pumping <b>1804</b> g.p.m. Estimated maximum yield <b>1804</b> g.p.m.	
Coarse Sand & Gravel			149	157	13. Water sample submitted: <b>1804</b> g.p.m. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date	
Clay & Sand & Gravel Mix			157	170	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> Inches above grade	
Clay			170	173	15. Well grouted? <input checked="" type="checkbox"/> <b>Clay</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> <del>XXXX</del> Depth: From <b>0</b> ft. to <b>10</b> ft.	
Cemented Sand & Gravel			173	177	16. Nearest source of possible contamination: ft. <b>9000</b> Direction <b>E</b> Type <b>KK Farm</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Coarse Sand & Gravel			177	197	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Floway</b> Model number <b>056118</b> HP <b>100</b> Volts <b>480</b> Length of drop pipe <b>240</b> ft. capacity <b>550</b> g.p.m. Type: <b>11 stage 10" DOH Bowl</b> <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Clay & Sandy Clay			197	217	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>WesternWell &amp; Pump</b> <b>245</b> Business name License No. Address <b>Box 8852 Colby, KS</b> Signed <b>Darryl Berry</b> Date <b>9-22-76</b> Authorized representative	
Coarse Sand & Gravel			217	235		
Clay			235	237		
Coarse Sand & Gravel			237	242		
Clay			242	248		
Coarse Sand & Gravel			248	264		
Ochre & <del>XXXX</del> Shale			264	271		
BROCK 264'						
18. Elevation:			19. Remarks:			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5