

1 LOCATION OF WATER WELL: County: Sherman Fraction: SW 1/4 NW 1/4 SE 1/4 Section Number: 25 Township Number: 83 Range Number: 40 E(W)

Distance and direction from nearest town or city street address of well if located within city?

1/2 West of HWY 27 on Rd 63 - 3/8 mile North

2 WATER WELL OWNER: Brent W. Linin
 RR#, St. Address, Box #: 1825 W. HWY 24
 City, State ZIP Code: Goodland, Ks. 67435

Global Positioning Systems (decimal degrees, min. of 4 digits)
 Latitude: 264181 E
 Longitude: 4356539 N
 Elevation: 3725'
 Datum: NAD 83 Zone 14
 Data Collection Method: GPS

3 MARK WELL'S LOCATION WITH AN "X" IN SECTION BOX:

N			
	NW		NE
W		X	
	SW		SE
S			

4 DEPTH OF WELL 274 ft.
 WELL'S STATIC WATER LEVEL 199' ft.
 WELL WAS USED AS:
 1 Domestic 5 Public Water Supply 9 Dewatering
 2 **Irrigation** 6 Oil Field Water Supply 10 Monitoring
 3 Feedlot 7 Domestic (Lawn & Garden) 11 Injection Well
 4 Industrial 8 Air Conditioning 12 Other _____

Was a chemical/bacteriological sample submitted to Department? Yes No _____

5 TYPE OF BLANK CASING USED:
 1 Steel 3 RMP (SR) 5 Wrought 7 Fiberglass 9 Other (Specify below)
 2 **PVC** 4 ABS 6 Asbestos-Cement 8 Concrete Tile

Blank casing diameter 16 in. Was casing pulled? Yes No _____ If yes, how much 8'
 Casing height above or below land surface 96 in.

6 GROUT PLUG MATERIAL: 1 Neat cement 2 Cement grout 3 **Bentonite** 4 Other _____

Grout Plug Intervals: From 274 ft. to 175 ft., From 10 ft. to 7 ft., From _____ to _____ ft.

What is the nearest source of possible contamination:
 1 Septic tank 6 Seepage pit 11 Fuel Storage 16 Other (specify below)
 2 Sewer lines 7 Pit privy 12 Fertilizer storage
 3 Watertight sewer lines 8 Sewage lagoon 13 Insecticide storage
 4 Lateral lines 9 Feedyard 14 **Abandoned water well**
 5 Cess pool 10 Livestock pens 15 Oil well/Gas well

Direction from well? South
 How many feet? 150'

FROM	TO	PLUGGING MATERIALS	FROM	TO	PLUGGING MATERIALS
274'	180'	Chlorinated Gravel			
180'	175'	Bentonite Chips			
175'	10'	Native Clays			
10'	8'	Bentonite Chips			
8'	8'	1/4" Steel Plate, Sealed to Casing			
8'	7'	Chip & Clay Tailings			
7'	0'	Native Clays			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was plugged under my jurisdiction and was completed on (mo/day/year) 7-26-13 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 633. This Water Well Record was completed on (mo/day/year) 9-5-13 under the business name of DMW Well + Pump Service by (signature) Jerry T. Hudnell

INSTRUCTIONS: Use typewriter or ballpoint pen. Please press firmly and print clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Ste. 420, Topeka, Kansas 66612-1367. Telephone: 785/296-5522. Send one to Water Well Owner and retain one for your