


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

ACC

1. Location of well:		County <b>Sheridan</b>	Fraction <b>SW 1/4 SW 1/4 NE 1/4</b>	Section number <b>22</b>	Township number <b>T 9 S R 28</b>	Range number <b>28</b>	<b>NE/W</b>
2. Distance and direction from nearest town or city: <b>6 South; 1/2 East; 1/2 South</b> Street address of well location if in city:			3. Owner of well: <b>Clem Ochs</b> R.R. or street: City, state, zip code: <b>Hoxie, Kansas</b>		6. Bore hole dia. <b>30</b> in. Completion date <b>8-10-76</b> Well depth <b>212</b> ft.		
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material			From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Clay			0	60	9. Casing: Material <b>Steel</b> Height: Above <del>ground</del> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>.188</b> lbs./ft. Dia. <b>16</b> in. to <b>142</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>#7</b>		
Fine Sand, Clay, Streaks of Gravel			60	90	10. Screen: Manufacturer's name <b>Brown</b> Type <b>Bridge</b> Dia. <b>16"</b> Slot/gauze <b>10%</b> Length <b>60'</b> Set between <b>142</b> ft. and <b>202</b> ft. <b>10' R. John. 202</b> ft. and <b>212</b> ft.		
Clay			90	100	Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/2 x 5/8</b>		
Clay, Streaks of Sand Stone			100	120	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>131</b> ft. below land surface Date <b>8-11-76</b>		
Clay, Streaks of Med. Gravel			120	140	12. Pumping level below land surfaces: <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. <b>206</b> ft. after <b>2</b> hrs. pumping <b>325</b> g.p.m. Estimated maximum yield <b>325</b> g.p.m.		
Fine Sand, Clay			140	160	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date		
Coarse Sand			160	164	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> Inches above grade		
Clay			164	200	15. Well grouted? <input checked="" type="checkbox"/> X With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> X Bentonite <input checked="" type="checkbox"/> X Clay Depth: From <b>0</b> ft. to <b>10</b> ft.		
Med. Gravel, Streaks of Clay			200	209	16. Nearest source of possible contamination: ft. <b>4500</b> Direction <b>S</b> Type <b>House</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Ochre & Shale			209	212	17. Pump: <input checked="" type="checkbox"/> X Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Western Well &amp; Pump 245</b> Business name License No. Address <b>Box 852, Colby, KS 67701</b> Signed <b>Dale Berry</b> Date <b>9-22-76</b> Authorized representative		
18. Elevation:		19. Remarks: <b>BROCK 209'</b>					
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley							

T 9 S R 28 E Sec 22 SW 1/4 NE

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5