

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
K.S. 82a-1201-1215

Kansas Department of Health and Environment
Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

TWP: Parnell

BAA

* Location of well:		County Sheridan	Fraction NE 1/4 NE 1/4 NW 1/4	Section number 20	Township number T 9	Range number S R 29	NW
* Distance and direction from nearest town or city: From K24 & Seguin 8 1/2 miles South and 1/4 East Street address of well location if in city: Well behind house.				3. Owner of well: Lawrence Thummel R.R. or street: City, state, zip code: Seguin, Kansas			
4. Locate with "X" in section below: Sketch map: N W E S 1 Mile				6. Bore hole dia. 30 in. Completion date 5/14/76 Well depth 107 ft.			
5. Type and color of material				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary			
TOP SOIL AND SANDY CLAY				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
MEDIUM GRAVEL				9. Casing: Material Steel Height: Above XXXX Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 188 lbs./ft. Dia. 16 in. to 37 ft. depth Well Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 7 gauge			
MEDIUM GRAVEL & SMALL SANDSTONE STREAKS & SANDY				10. Screen: Manufacturer's name Brown			
CLAY TRACES				Type Regular Dia. 16" Slot 10% Length 60' Set between 37 ft. and 97 ft. 10' Cook 97 ft. and 107 ft. Gravel pack? YES Size range of material 1/4 x 5/8 30% #1			
MEDIUM GRAVEL				11. Static water level: <input type="checkbox"/> mo./day/yr. 14 ft. below land surface Date 5-30-76			
SANDSTONE				12. Pumping level below land surfaces: 95 ft. after 2 hrs. pumping 1073 g.p.m. 104 ft. after 2 hrs. pumping 990 g.p.m. Estimated maximum yield 1073 g.p.m.			
MEDIUM GRAVEL				13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date			
SANDY CLAY AND SANDSTONE TRACES				14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade			
FINE SAND AND MEDIUM GRAVEL & SANDY CLAY TRACES				15. Well grouted? <input checked="" type="checkbox"/> Clay With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> XXXXX Depth: From 0 ft. to 10 ft.			
FINE SAND AND SANDY CLAY & SANDSTONE TRACES				16. Nearest source of possible contamination: ft. 1000 Direction West SW Type Feedlot Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
MEDIUM GRAVEL LOOSE				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Floway Model number 7662 HP 80 Volts <input type="checkbox"/> Length of drop pipe 90 ft. capacity 600 g.p.m. Type: <input type="checkbox"/> 10 stage 10" D.O.H. Bowl <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
(Use a second sheet if needed)				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Western Well & Pump, INC. 245 Business name License No. Address P.O. Box 852 Colby, KS. Signed Dolly Berry Date 6-9-76 Authorized representative			
18. Elevation:		19. Remarks:					
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

1-9
 29
 22
 1/4 1/4 1/4 1/4
 NE 1/4 NW 1/4