


LOCATION OF WATER WELL		Fraction	Section Number		Township Number		Range Number	
County: Thomas		SW 1/4 SW 1/4 SE 1/4	13		T 9 S		R 31 EW	
Distance and direction from nearest town or city? From Menlo				Street address of well if located within city? N/A				
WATER WELL OWNER: Don Ostmeyer				Board of Agriculture, Division of Water Resources				
R#, St. Address, Box # : Oakley, Kansas 67748				Application Number: 35233				
DEPTH OF COMPLETED WELL: 208 ft. Bore Hole Diameter: 16 in. to 208 ft. and in. to ft.								
Well Water to be used as:				11 Injection well				
1 Domestic 3 Feedlot 6 Oil field water supply 8 Air conditioning 9 Dewatering 12 Other (Specify below)								
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well								
Well's static water level: 95 ft. below land surface measured on 5 month 1 day 81 year								
Pump Test Data: Well water was 153 ft. after 4 hours pumping 1100 gpm								
St. Yield 1100 gpm: Well water was 133 ft. after 5 hours pumping 654 gpm								
TYPE OF BLANK CASING USED:				Casing Joints: Glued Clamped				
1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded								
2 PVC 4 ABS 7 Fiberglass Threaded								
Blank casing dia: 16 in. to 138 ft. Dia in. to ft. Dia in. to ft.								
Casing height above land surface: 12 in., weight lbs./ft. Wall thickness or gauge No. 188								
TYPE OF SCREEN OR PERFORATION MATERIAL:				7 PVC 10 Asbestos-cement				
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)								
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)								
Screen or Perforation Openings Are:				5 Gauzed wrapped 8 Saw cut 11 None (open hole)				
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes								
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)								
Screen-Perforation Dia: 16 in. to ft. Dia in. to ft. Dia in. to ft.								
Screen-Perforated Intervals: From W A Brown 138 ft. to 198 ft. From ft. to ft.								
From Johnson 198 ft. to 208 ft. From ft. to ft.								
Gravel Pack Intervals: From 10 ft. to 208 ft. From ft. to ft.								
From ft. to ft. From ft. to ft.								
GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Cement								
Grouted Intervals: From 0 ft. to 10 ft. From ft. to ft. From ft. to ft.								
What is the nearest source of possible contamination:				10 Fuel storage 14 Abandoned water well				
1 Septic tank 4 Cess pool 7 Sewage lagoon 11 Fertilizer storage 15 Oil well/Gas well								
2 Sewer lines 5 Seepage pit 8 Feed yard 12 Insecticide storage 16 Other (specify below)								
3 Lateral lines 6 Pit privy 9 Livestock pens 13 Watertight sewer lines								
Direction from well: Northeast How many feet: 3600 ? Water Well Disinfected? Yes No X								
Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, date sample								
Was submitted month day year Pump Installed? Yes No X								
Yes: Pump Manufacturer's name Model No. HP Volts								
Depth of Pump Intake ft. Pumps Capacity rated at gal./min.								
Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other								
CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was								
Completed on XX May XX 2 day 1981 year								
And this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 245								
This Water Well Record was completed on 10 month 15 day 1981 year under the business								
Name of Western Well and Pump, Inc. by (signature) Roy F. Demer								
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG				
		0 55 Clay		168 170 Med. to cr. gravel				
		55 65 Fine sand to cr. gravel		170 171 Sand stone				
		65 68 Clay		171 175 Med to cr. gravel				
		68 92 Fine Sand to cr. gravel		175 176 Sandstone				
		92 94 Clay		176 203 Med. to cr. gravel				
		94 121 Fine sand to med. gravel		203 Ochre & Shale				
		101 123 Sandstone						
		123 143 Fine Sand to coarse gravel						
		143 144 Sandstone						
		144 167 Med to coarse Gravel						
167 168 Sandstone								
ELEVATION: 95 ft. 2 ft. 3 ft. 4 ft.				(Use a second sheet if needed)				
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.								