


1 LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number
County: Thomas		NW 1/4 NW 1/4 SE 1/4	11	T 9 S	R 34 E/W
Distance and direction from nearest town or city? Mingo 6 1/2 mi. west and 1 1/2 North			Street address of well if located within city? N/A		
2 WATER WELL OWNER:		Harvey Kistler			
RR#, St. Address, Box # :		R.R. 2			
City, State, ZIP Code :		Colby, Kansas 67701			
Board of Agriculture, Division of Water Resources		Application Number: 32,652			
3 DEPTH OF COMPLETED WELL		257 ft. Bore Hole Diameter 36 in. to 257 ft. and in. to ft.			
Well Water to be used as:		5 Public water supply 8 Air conditioning 11 Injection well			
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
Well's static water level 143 ft. below land surface measured on 2 month 5 day 80 year		Pump Test Data			
Est. Yield 1500 gpm		Well water was 171 ft. after 1 1/2 hours pumping 650 gpm			
Well water was 203 ft. after 2 hours pumping 1000 gpm		4 TYPE OF BLANK CASING USED:			
1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below)		Casing Joints: Glued Clamped Welded Threaded			
2 PVC 4 ABS 7 Fiberglass		Blank casing dia 16 in. to 177 ft. Dia 12 in. weight lbs./ft. Wall thickness or gauge No 219			
Casing height above land surface		TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)		2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)			
Screen or Perforation Openings Are:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes		2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)			
Screen-Perforation Dia in. to ft. Dia in. to ft. Dia in. to ft.		Screen-Perforated Intervals: From 177 W A Brown ft. to 237 ft. From 237 Johnson ft. to 257 ft. From 10 ft. to 257 ft. From ft. to ft.			
Gravel Pack Intervals: From 10 ft. to 257 ft. From ft. to ft. From ft. to ft.		5 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Cement			
Grouted Intervals: From 0 ft. to 10 ft. From ft. to ft. From ft. to ft.		What is the nearest source of possible contamination:			
1 Septic tank 4 Cess pool 7 Sewage lagoon 11 Fertilizer storage 15 Oil well/Gas well		2 Sewer lines 5 Seepage pit 8 Feed yard 12 Insecticide storage 16 Other (specify below)			
3 Lateral lines 6 Pit privy 9 Livestock pens 13 Watertight sewer lines		Direction from well SE How many feet 5200 ? Water Well Disinfected? Yes No X			
Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, date sample was submitted month day year: Pump Installed? Yes X No		If Yes: Pump Manufacturer's name Floway Model No. 10-10 DOH HP 75 Volts 440			
Depth of Pump Intake 255 ft. Pumps Capacity rated at 600 gal./min.		Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other			
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 9 month 5 day 80 year		and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 245			
This Water Well Record was completed on 10 month 2 day 80 year under the business name of Western Well & Pump Inc. by (signature) Roy F. Senior Jr.		7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			
		FROM TO LITHOLOGIC LOG FROM TO LITHOLOGIC LOG			
		0 30 Clay 250 255 Coarse Sand - Med Gravel			
		30 70 Coarse Sand & Gravel 255 Ochre			
		70 120 Clay, Sandstone Str.			
		120 143 Sandstone & Clay			
		143 159 Fine Sand, Clay, Sandstone			
		159 175 Coarse sand & med gravel			
		175 196 Fine & Coarse sand, Med Gr			
		196 201 Sandstone			
		201 205 Coarse Sand			
		205 214 Sandy Clay & Sandstone Str.			
		214 250 Fine Sand & Sandy Clay			
ELEVATION:		Depth(s) Groundwater Encountered 1. 160 ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)			
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					