


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Thomas	Fraction NE 1/4 SW 1/4 SE 1/4	Section number #13	Township number T 9 S R 34	Range number 34
2. Distance and direction from nearest town or city: 8 3/4 miles South & 1/4 mile West Street address of Well location if in city:			3. Owner of well: Clarence Cersovsky R.R. or street: RFD #2 City, state, zip code: Colby, Kansas 67701			
4. Locate with "X" in section below: 			Sketch map:			
5. Type and color of material			From	To	6. Bore hole dia. 36 in. Completion date 11-6-75 Well depth 275 ft.	
Clay			0	35	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary	
Coarse sand & gravel			35	40	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Clay			40	56	9. Casing: Material steel Height Above or below	
Coarse sand & gravel			56	79	Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight .188 lbs./ft.	
Clay			79	83	Dia. 16 in. to 165 ft. depth Wall Thickness 1/2 inches or Dia. 16 in. to 165 ft. depth gauge No. 17	
Coarse sand & gravel			83	93	10. Screen: Manufacturer's name W. A. Brown Type perforated Dia. 16 " Slot/gauze 10 % Length 100 ' Set between 165 ' ft. and 265 ' ft. 10' of cook ft. and 275 ' ft. Gravel pack? yes Size range of material 1/8x1/2	
Clay			93	98	11. Static water level: 109 ' ft. below land surface Date 11-7-75	
Coarse sand & gravel			98	106	12. Pumping level below land surfaces: 167 ' ft. after 2 hrs. pumping 1370 g.p.m. 167 ' ft. after 1 hrs. pumping 1800 g.p.m. Estimated maximum yield 1800 g.p.m.	
Clay & sand streaks			106	120	13. Water sample submitted: Yes ☒ No ☐ Date 11-7-75	
Medium to coarse sand & gravel			120	130	14. Well head completion: 12 inches above grade ☐ Pitless adapter 12 inches above grade	
Sandy clay			130	143	15. Well grouted? yes & clay With: ☒ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
Medium to coarse sand & gravel			143	149	16. Nearest source of possible contamination: ft. 1500 Direction SE Type Farm Well disinfected upon completion? Yes ☒ No ☐	
Clay			149	151	17. Pump: Not installed Manufacturer's name Floway Model number 11-10DOH HP 100 Volts 115 Length of drop pipe 270 ft. capacity 550 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Medium to coarse sand & gravel & clay streaks			151	165	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Western Well & Pump, Inc. 245 Business name P.O. Box 852, Colby, Ks. License No. 1/4 NE 34 E 1 S 3 Address 1/4 NE 34 E 1 S 3 Signed Roy F. Senia Date Jan 11 1976 Authorized representative	
Clay			165	168		
Coarse sand & gravel			168	180		
Clay			180	188		
Medium to coarse sand			188	196		
Medium to coarse sand & clay streaks			196	212		
Clay			212	216		
Fine to medium sand & clay streaks			216	225		
Clay			225	229		
Fine to medium sand & clay streaks			229	240		
Sandy clay & fine to medium sand			240	251		
Fine to medium sand & sand stone streaks			251	254		
Medium to coarse sand & gravel			254	261		
Clay			261	262		
Medium to coarse sand & gravel			262	268		
Clay			268	269		
Medium to coarse sand & gravel			269	271		
Ochre & Shale			271	275		
18. Elevation:			19. Remarks: ground elec. at well = 3,167' BRUCK 3168 (TOPO)			
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5