


ABA

1 LOCATION OF WATER WELL		Fraction NE ¼ NW ¼ NE ¼	Section Number 14	Township Number T 9 S	Range Number R 34 E/W
County: Thomas		Distance and direction from nearest town or city? Mingo 6 ¼ West, ¼ South		Street address of well if located within city? N/A	
2 WATER WELL OWNER:		Harvey Kistler			
RR#, St. Address, Box # :		R. R. 2			
City, State, ZIP Code :		Colby, KS 67701			
		Board of Agriculture, Division of Water Resources Application Number: 32,652			
3 DEPTH OF COMPLETED WELL.		305 ft. Bore Hole Diameter. 36 in. to 305 ft., and in. to ft.			
Well Water to be used as:		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
Well's static water level 106 ft. below land surface measured on 10 month 24 day 79 year					
Pump Test Data		Well water was 155 ft. after 1 ½ hours pumping 1300 gpm			
Est. Yield 2000 gpm		Well water was 201 ft. after 3 hours pumping 2000 gpm			
4 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile Casing Joints: Glued Clamped 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded 2 PVC 4 ABS 7 Fiberglass Threaded			
Blank casing dia 16 in. to 185 ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 12 in., weight 32 lbs./ft. Wall thickness or gauge No. 188					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)			
Screen or Perforation Openings Are:		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)			
Screen-Perforation Dia 16 in. to ft., Dia in. to ft., Dia in. to ft.					
Screen-Perforated Intervals: 4 From 195 ft. to 275 ft., From ft. to ft.					
6 From 275 ft. to 305 ft., From ft. to ft.					
Gravel Pack Intervals: From ft. to ft., From ft. to ft.					
From 10 ft. to 305 ft., From ft. to ft.					
5 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other Concrete			
Grouted Intervals: From 0 ft. to 10 ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Fuel storage 14 Abandoned water well 1 Septic tank 4 Cess pool 7 Sewage lagoon 11 Fertilizer storage 15 Oil well/Gas well 2 Sewer lines 5 Seepage pit 8 Feed yard 12 Insecticide storage 16 Other (specify below) 3 Lateral lines 6 Pit privy 9 Livestock pens 13 Watertight sewer lines Farmstead			
Direction from well SE. How many feet 3000? Water Well Disinfected? Yes No X					
Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, date sample was submitted month day year: Pump Installed? Yes X No					
If Yes: Pump Manufacturer's name Floway Model No. 7-12DOH HP 153 Volts					
Depth of Pump Intake 267 ft. Pumps Capacity rated at gal./min.					
Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other					
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 10 month 21 day 79 year					
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 245					
This Water Well Record was completed on 1 month 24 day 80 year under the business name of Western Well & Pump, Inc. by (signature) Roy E. Lanius					
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:					
					
ELEVATION:					
FROM TO LITHOLOGIC LOG FROM TO LITHOLOGIC LOG					
0 35 Clay		229 232 Clay			
35 55 Fine, Coarse Sand & Clay		St. 232 246 Coarse Sand, Gravel, Layers of Cemented Sand & Gravel			
55 97 Sand, Gravel & Clay					
97 116 Clay, Sand & Sandstone St.		246 284 Fine Med. Sand, Clay & Cement Streaks			
116 140 Medium Coarse Sand & Gravel					
140 145 Clay		284 288 Coarse Sand			
145 177 Fine to Coarse Sand		288 290 Clay			
177 182 White Clay		290 302 Coarse Sand & Gravel			
182 196 Coarse Sand & Small Gravel		302 305 Ochre & Shale			
196 201 Clay					
201 229 Coarse Sand & Gravel		BROOK 302			
Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. 4. ft.		(Use a second sheet if needed)			
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

9

R

34

EW

SEC.

14

NE

1/4

NE

1/4

1/4