

(316) 268-3000
FAX: (316) 268-64551700 N. WATERFRONT PARKWAY
SUITE 600
WICHITA, KANSAS 67206-5514Scale 1:240 (5"=100') Imperial
Measured Depth Log

Well Name: SC- LR #1-33
Location: 945°FWL 2684° FWL 33-16S-33W, Scott County, Kansas
License Number: API: 15-171-21111
Spud Date: 5-15-13
Surface Coordinates: Lat: 38.6244192 Long: -100.9711741
Bottom Hole Coordinates: Vertical hole

Ground Elevation (ft): 3064'
Logged Interval (ft): 250'
Formation: Mississippian at RTD
Type of Drilling Fluid: Chemical

K.B. Elevation (ft): 3073'
To: RTD
Total Depth: 4840'

Drilling Completed: 11-24-14

Printed by MUD.LOG from WellSight Systems 1-800-447-1534 www.WellSight.com

GEOLOGIST

Name: Bob Schreiber
Company: Independent
Address: 268 NE 220 Rd
Holsington, KS 67544
620-653-7691

COMMENTS

Contractor: Duke Drig Rig #4 #
Pusher: Rich Wheeler
Surface Casing: 8 5/8" set at 221' w/165sxs
Production Casing: 5 1/2" set @ 4833' cmnt w/170 sxs
Mud by: MudCo
DST's by: Diamond Testing
Logs by: Recon (DIL, CN-CD, ML,SONIC)
RTD= 4840'
LTD= 4839'

FORMATION TOPS

FORMATION	SAMPLE TOPS		LOG TOPS	
	Depth	Datum	Depth	Datum
Stone Corral	2412'	+659	2410'	+663
Stone Corral	2433'	+638	2430'	+643
Topeka	3735	-662	3734	-661
Heebner Shale	3970'	-899	3970'	-897
Lansing	4015'	-944	4010'	-937
Muncie Creek Shale	4196'	-1125	4194'	-1121
Shale	4295'	-1224	4294'	-1222
Hushpuckney Shale	4342'	-1269	4351'	-1278
Marmaton	4416'	-1345	4412'	-1339
Upper Fort Scott	4519'	-1446'	4518'	-1445
Little Osage Shale	4394'	-1449'	4540'	-1467
Excelllo Shale	4558'	-1485	4558'	-1485
Johnson Zone	4631'	-1558	4631'	-1558
Morrow	4699'	-1626'	4698'	-1625
Mississippian	4736'	-1663	4736'	-1663
RTD	4840'	-1867		
LTD			4839'	-1766

