



MICRO RESISTIVITY LOG

Company	Triple Crown Operating, LLC.
Well	Darlene #1-34
Field	Unnamed
County	Ness
State	Kansas
Location:	API # : 15 135 26097
Permanent Datum	1583 FNL & 335 FWL
Log Measured From	NE-NW-SW-NW
Drilling /Measured From	KB 5 AGL
Elevation	2244'
Other Services	DIL CDNL
Date	3/19/21
Run Number	One
Depth Driller	4419'
Depth Logger	4421'
Bottom Logged Interval	4419'
Top Log Interval	2500'
Casing Driller	8 5/8" @ 1412'
Casing Logger	1425'
Bit Size	7 7/8"
Type Fluid in Hole	Chemical
Density / Viscosity	9.3/60
pH / Fluid Loss	10.0/6
Source of Sample	Calculated
Rim @ Meas. Temp	1.0 @ 70degf
Rim @ Meas. Temp	0.8 @ 70degf
Rim @ Meas. Temp	1.3 @ 70degf
Source of Rmt / Rmc	Calculated
Rim @ BHT	0.6 @ 115degf
Time Circulation Stopped	12:00 p.m
Time Logger on Bottom	5:50 p.m
Maximum Recorded Temperature	115degf
Equipment Number	T605
Location	Hays, KS
Recorded By	C. Patterson
Witnessed By	Mr. Sean Deenihan
	Mr. Chris Johnson

<<< Fold Here >>>

All interpretations are opinions based on inferences from electrical or other measurements and we cannot and do not guarantee the accuracy or correctness of any interpretation, and we shall not, except in the case of gross or willful negligence on our part, be liable or responsible for any loss, costs, damages, or expenses incurred or sustained by anyone resulting from any interpretation made by any of our officers, agents or employees. These interpretations are also subject to our general terms and conditions set out in our current Price Schedule.

Comments


Bazine, KS 3 mi. East to GG Rd.,South on GG Rd. 10.3mi.(Just Past 10 Rd.), East into Location

Thanks for using Gemini Wireline LLC
785-625-1182




MAIN PASS

Database File: tcdarlene#1-34oh.db
Dataset Pathname: pass4
Presentation Format: kml
Dataset Creation: Fri Mar 19 18:06:50 2021
Charted by: Depth in Feet scaled 1:240



REPEAT SECTION

Database File: tcdarlene#1-34oh.db
Dataset Pathname: pass3
Presentation Format: kml
Dataset Creation: Fri Mar 19 17:53:33 2021
Charted by: Depth in Feet scaled 1:240



Calibration Report

Database File: tcdarlene#1-34oh.db
Dataset Pathname: pass4
Dataset Creation: Fri Mar 19 18:06:50 2021

Microlog Calibration Report

Serial-Model: 1600-Pengo
Performed: Fri Mar 19 17:52:05 2021

	Readings			References			Results	
	Zero	Cal		Zero	Cal		m	b
Normal	0.0001	0.4834	V	0.0000	10.0000	Ohm-m	20.6896	-0.0021
Inverse	-0.0304	0.6370	V	0.0000	10.0000	Ohm-m	14.9851	0.4552
Caliper	2.9973	6.1045	V	7.6500	15.0000	in	2.3655	0.5600

Gamma Ray Calibration Report

Serial Number: 2001
Tool Model: OH
Performed: Sun Nov 12 14:26:41 2017

Calibrator Value: 1.0 GAPI

Background Reading: 0.0 cps
Calibrator Reading: 1.0 cps

Sensitivity: 0.7000 GAPI/cps

Sensor	Offset (ft)	Schematic	Description	Length (ft)	O.D. (in)	Weight (lb)
GR	8.13		CHD-None	0.75	1.50	5.00
MCAL	1.30		GR-OH (2001)	3.56	3.25	40.00
MI	1.30		2001			
MN	1.30		ML-Pengo (1600)	6.97	3.50	100.00

Dataset: tcdarlene#1-34oh.db: field/well/run1/pass4
Total length: 112.88 ft
Total weight: 145.00 lb
O.D.: 3.50 in